

Vanderbilt University Medical Center PLANNING | DESIGN | CONSTRUCTION

POLICIES AND PROCEDURES

SUBJECT: INTERIM LIFE SAFETY IMPLEMENTATION POLICY

POLICY # PDC-011

EFFECTIVE DATE: January 31, 2011

Revised Date: 25 JUNE 2019

POLICY

All Construction Managers (CM), contractors and subcontractors who work in the Vanderbilt University Medical Center (VUMC) must perform this work in accordance with the VUMC "Interim Life Safety Implementation Policy" (SA 40-10.05).

PROCEDURE

The purpose of this policy is to provide a comprehensive plan for the Preconstruction assessment and appropriate implementation of the Interim Life Safety Measures (ILSM) policy for Vanderbilt University Medical Center (VUMC) construction and renovation projects.

I. Specific Information

- A. The implementation of Interim Life Safety Measures is required in or adjacent to all construction areas and throughout buildings with existing Life Safety Code deficiencies.
- B. When the VUMC Staff member who is responsible for the project determines that a building's life safety system has been, or will be impaired, the "ILSM Application Matrix" must be completed.
- C. In keeping with the Interim Life Safety Policy, the contractor must post the ILSM Daily Egress Inspection Log at the entrance to the construction site. The contractor's authorized representative must initial the ILSM Daily Egress Inspection Log each day to document that he has performed a daily inspection to ensure all paths of egress remain unobstructed. All of the ILSM Daily Egress Inspection Log forms must be retained by the contractor and submitted to the PLANNING | DESIGN | CONSTRUCTION (PDC) Construction Coordinator at the completion of the project.